



सत्यमेव जयते

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण

(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)

National Highways Authority of India

(Ministry of Road Transport & Highways, Govt. of India)

क्षेत्रीय कार्यालय, ओडिशा / Regional Office, Odisha

301 - ए, तीसरी मंजिल, पाल हाईट्स, प्लॉट नं जे/7 जयदेव विहार, भुवनेश्वर-751013, ओडिशा

301-A, 3rd Floor, Pal Heights, Plot No : J/7, Jayadev Vihar, Bhubaneswar-751013, Odisha

दूरभाष/Ph.: 0674 - 2361470/570/670 (का/ओ)

ई-मेल/e-mail : roodisha@nhai.org, ronhaiodisha@gmail.com, मोबाइल /Web. : www.nhai.gov.in



NHAI/13011/54/RO/OD/ 1262+2025

06.06.2025

To

The Sr. Technical Director,
NIC Centre at MoRTH,
Transport Bhawan,
New Delhi 110001

Sub: Rimuli Koida section of NH-520: Proposal for permission for laying of Overhead 33 KV Electrical line of TPNODL from BRPL Chowk (Tanto) to Rugudi RSS - Reg

Ref: PD, PIU- Keonjhar letter no. 1832 dated 31.12.2024 & 854 dated 23.05.2025

Sir,

Please find enclosed herewith proposal of Executive Engineer, Joda Division, TPNODL regarding for laying of 33 KV electrical power cable along the NH from 191+750 to Km. 200+800 (RHS).

2. Accordingly, as per guidelines issued by MoRT&H vide F. No. RW/NH-33044/29/2015/S&R(R) dt. 22.11.2016, the application along with the recommendations of concerned PD/Consultants are enclosed herewith with request to hoist the same in the Ministry's Website for public comments within 30 days of uploading on the website.

This is issued with the approval of Regional Officer, Odisha.

Yours Sincerely,

Abinash
06.06.25

(Abinash Behera)
Manager (Tech)



सत्यमेव जयते

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण

(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)

National Highways Authority of India

(Ministry of Road Transport & Highways, Govt. of India)

क्षेत्रीय कार्यालय, ओडिशा / Regional Office, Odisha

301 - ए, तीसरी मंजिल, पाल हाईट्स, प्लॉट नं जे/7 जयदेव विहार, भुवनेश्वर-751013, ओडिशा

301-A, 3rd Floor, Pal Heights, Plot No : J/7, Jayadev Vihar, Bhubaneswar-751013, Odisha

दूरभाष/Ph.: 0674 - 2361470/570/670 (का/ओ)

ई-मेल/e-mail : roodisha@nhai.org, ronhaiodisha@gmail.com, मोबाइल /Web. : www.nhai.gov.in



NHAI/13011/54/RO/OD/ 1262/2025

06.06.2025

INVITATION OF PUBLIC COMMENTS

Sub: Rimuli Koida section of NH-520: Proposal for permission for laying of Overhead 33 KV Electrical line of TPNODL from BRPL Chowk (Tanto) to Rugudi RSS - Reg

Executive Engineer, Joda Division, TPNODL has submitted a proposal for laying of 33 KV electrical power cable along the NH from 191+750 to Km. 200+800 (RHS).

2. As per guidelines issued by MoRT&H vide F. No. RW/NH-33044/29/2015/S&R(R) dated 22.11.2016, the Highway Administration will put out the application in the public domain for 30 days for seeking claims and objections on grounds of public inconvenience, safety and general public interest.

3. In view of the above, the comments of public, if any, on the above-mentioned proposal are invited on below mentioned address:

The Regional Officer,
National Highways Authority of India,
Regional Office, Odisha
301-A, 3rd Floor, Pal Heights,
J/7, Jayadev Vihar, Bhubaneswar 751013, Odisha
e-mail: roodisha@nhai.org

This is issued with the approval of RO, Odisha.

A. Anand
06.06.25

Manager (Tech)
National Highways Authority of India,
Regional Office, Odisha
301-A, 3rd Floor, Pal Heights,
J/7, Jayadev Vihar, Bhubaneswar 751013

To,
The Project Director,
NHAI, Keonjhar.

Sub: Submission of Check list for getting approval/NOC for Construction of new 33KV O/H Line along the road of NH-520 from BRPL, Tanto To Rugudi PSS , Keonjhar.

Ref: Letter No- NHAI/11018/7/NH-215/PIU/KJR/1462

Date- 17.10.2024

Dear Sir,

With reference to above, we are submitting the check list duly fill up for Construction of new 33KV O/H Line and lay of Electrical UG Cable on NH-520 land for & necessary approval at your end.

CHECK LIST

S.no	ITEM	Information/Status	Remarks
1	General information		
1.1	Name &Address of the Applicant/Agency	TPNODL JoED, Joda, Keonjhar	
1.2	National Authority number	NH-520	
1.3	State	ODISHA	
1.4	Location	Existing Road from – BRPL,Tanto to Rugudi PSS	
1.5	Chainage in km	KM 191.750 to 200.800	
1.6	Length in meters	9000	
1.7	Width of available ROW	60M	4
	a) Left side from center line towards increasing chainage/km direction		
	b) Right side from center line towards increasing chainage /km direction	30M	
1.8	Proposal to lay underground electrical cable		
	a) Left side from center line towards increasing chainage/km direction		
	b) Right side from center line towards increasing chainage/km direction	28.9M	
1.9	Proposal to acquire land		
	a)Left side from center line	NA	
	b) Right side from center line	NA	
1.10	Whether proposal is in the same side where land is nor to be acquired	NA	
	If not then where to lay the cable		
1.11	Details of already laid services ,if any along the proposed route	NA	
1.12	Number of lanes existing	4 Lanes	
1.13	Proposed number of lanes(2 lane with paved shoulders	NA	
1.14	Service road existing or not	NA	
	If yes then which side	NA	

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader

Executive Engineer
Joda Electrical Division

S.no	ITEM	Information/Status	Remarks
	a)Left side from center line	NA	
	b) Right side from center line	NA	
1.15	Proposed service road	YES	
	a)Left side from center line	NA	
	b) Right side from center line	NA	
1.16	Whether proposal to lay water supply Pipe line/Electrical Cable is after the service road or between the service road and main carriageway	O/H line will laid along the road of NH	
1.17	The permission for laying of water supply pipe line/Electrical cable Shall be considered for approval/rejection based on the Ministry Circulars mentioned as above		
	a)Carrying of sewage/gas pipelines on highway bridges shall not be permitted as fumes/gases pipes can accelerate the process of corrosion or may cause explosions thus being much more injurious than leakage of water	No Sewage/Gas pipe lines on highway bridge will be carried.	
	b) Carrying of water pipes on bridges shall also be discouraged. However, if the water supply authorities seem to have no other viable alternative and approach the highway authority well in line before the design of the bridge is finalized they may be permitted to carry the pipeline on independent superstructure supported on extended portions of pier and abutments in such a manner that in the final arrangement enough free space around the superstructure of the bridge remains available for inspection and repairs..etc	No water pipe lines on the bridge shall be carried.	
	c) Services are not being allowed indiscriminate on the parapet/any part of the bridges.Safety of the bridges has to be kept in view while permitting various services along bridge. Approvals are to be accorded in this regard with the concurrence of the Ministry's Project Chief Engineers only.	Not Applicable	
1.18	If crossing of the road involved If Yes. It shall ne either encased in pipes or through structure or conduits specially built for that purpose at the expenses of the agency owning the line.	NA	
	a)Existing drainage structures not be allowed to carry the line.	YES, The existing structure will not be used to carry the line	
	b) Is it on a line normal NH	YES	
	c) Crossing Shall not be too near the existing structures on the National Highway ,the minimum distance being 15 meters.What is the distance from the existing structures	Crossing not required, all lines are to constructed along the road	
	d)The casing pipe or conduit pipe in the case of electric cable carrying the utility line shall be of steel, cast iron or reinforced cement concrete and have adequate strength	NA	

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader

Executive Engineer
Joda Electrical Division
TPNODL, Joda

S.no	ITEM	Information/Status	Remarks
	and be large enough to permit ready withdrawal of the carrier pipe/cable.		
	e)Ends of the casing/Conduit pipe should be sealed from the outside, so that it does not act as a slope of the fills	Yes, It will be sealed on both side.	
	f)The casing/conduit pipe should be as minimum extend from drain to drain in cuts and toe slope in the fills	Yes, will be followed.	
	g)The top of the casing/conduit pipe should be at least 1.2 meter below the surface of the road subject to being at least 0.3 m below the drain inverts.	NA	
	h)Crossing shall be by boring method(HDD) specially where the existing road pavement is of cement concrete or dense bituminous concrete type.	NA	
	I)The casing/conduit pipe shall be installed with an even bearing throughout its length and in such a manner as to prevents the formation of waterway along it.	Yes	
2	Document/Drawing enclosed with the proposal	Yes,3sets	
2.1	Cross section showing the size of trench for open trenching method (Is it normal size of 1.2 m depth/0.3m wide)	NA	
	I) Should not be greater than 60 cm wider than the outer diameter of the pipe	NA	
	II)Location as closer to the extreme edge of the right-of-way as possible but not less than 15 meter from the center lines of the nearest carriageway.	NA	
	III) Shall not be permitted to run along the National Highways when the road formation is situated in double cutting. Nor shall these be laid over the existing culverts and bridges.	NA	
	IV)These should be so laid that their top is at least 0.6 meter below the ground level so as not to obstruct drainage of the road land.	NA	
2.2	Cross section showing the size of pit and location of cable for HDD method	Shown in the Enclosed drawing.	
2.3	Strip plan/Route plan showing Water supply pipe line/Electrical Cable Chainage, width of ROW, distance of proposed cable from the edge of ROW, important mile stone,intersecting,cross drainage works etc.	As per the Dwg enclosed.	
2.4	Methodology for laying of showing water supply pipe etc.	NA	
2.4.1	Open trenching methods(May be allowed in utility corridor only where pavemeter is neither cement concrete type. If yes, Methodology of refilling of trench.	NA	
	a)The trench width should be at least 30cm,but not more than 60cm wider than the outer diameter of the pipe.	Yes	
	b)For filling of the trench, Beeding shall be to depth of not less than 30cm it shall consist granular material	YES	

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader

Executive Engineer
Joda Electrical Division,
TBNQDI, Jodhpur

S.no	ITEM	Information/Status	Remarks
	unsuitable soil and rock edge should be excavated and replaced by selected material.		
	c)The back shall be completed two stages (I) Side-fill to the level of the top of the pipe and (II) overfill to the bottom of the road crust.	Ok	
	d) 95% of the proctors Density. Overfill shall be connected to the same density as the material that had been removed consolidation by saturation or ponding will not be permitted.	Ok	
	e)The road crust shall be built to the same strength as the existing crust on either side of the trench. Care shall be taken to avoid the formation of a clip at the trench.	Ok	
	f)The excavation shall be protected by flagman, signs and barricades and red lights curing night hours.	Ok	
	g)If required , a diversion shall be constructed at the expense of agency owning the utility line.	Ok	
2.4.2	Horizontal Directional Drilling(HDD) Method	NA	
2.4.3	Laying of Water Supply Pipe line/Electrical Cable through HD Works and method of laying.	NA	
	a)On Approaches the water mains/cables shall be carried along a line as close to the right way as possible up to a distance of 30m from the bridge and subject to all other stipulations in this Ministry's guidelines issued with letter no NH-HI/P/66/76 dated 19.11.197	Yes , Will be followed.	
3	Draft license agreement signed by two witnesses.	Enclosed	
4	Performance Bank Guarantee in favour of NHAI submitted @Rs.50/- per running meter (Parallel to NH) and Rs.1,00,000/- per crossing of NH,for a period of one year initially (Extendable if required till satisfactory completion laying the cables /ducts by proper filling and compaction, clearing debris/loose earth produced due to execution trenching at least 50m away from the edge of the right of way. No payment shall be payable by the NHAI to the license of clearing debris/loose earth	YES Agreed for submission of performance BG as per the last Month/NHAI Guideline	
4.1	Performance BG as per above obtained	In Conformity with NHAI	
4.2	Confirmation of BG has been obtained as per NHAI guidelines.	Yes	
5	Affidavit/Undertaking from the applicant for carrying out the work.	Yes	
5.1	Not to damage other utility, If damaged then to pay losses either to NHAI or to the concerned agency	Yes	
5.2	Renewal of Bank Guarantee.	Renewal to be done after its validity lapses	
5.3	Confirming all standard condition of NHAI guidelines	Yes	
5.4	Shifting of water supply pipe line/Electrical cable as and when required.	Yes, It will be carried out if required.	
5.5	Shifting due to 6 lanning/widening of NH.	Yes	

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader

Executive Engineer
Joda Electrical Division
TPNODL, Joda

S.no	ITEM	Information/Status	Remarks
5.6	Indemnity against all damages and claims clause(XXLV)	Yes	
5.7	Traffic movement during laying of Water Supply pipe line/Electrical cable to manage by the applicant.	Yes, The same will be managed at the time of work execution.	
5.8	If any claim is raised by the concessionaire then the same has to be paid by the applicant.	Yes	
5.9	Prior approval of the NHAI shall be obtained before undertaking any work of installation, shifting or repairs or alternations to the showing water supply pipe line/Electrical cable located in the National Highway right of ways.	Yes, Necessary permission to be taken before starting the work.	
5.10	Expenditure ,if any incurred by NHAI for repairing and damage caused to the National Highway by the laying maintenance or shifting of the water supply pipe line/Electrical Cable will be borne by the agency owning the line.	Yes	
5.11	If the NHAI considers it necessary in future to move the utility line for any work of improvement or repairs to the road, it will be carried out as desired by the NHAI at the agency owning the utility line within a reasonable time (not exceeding 60 days) of the intimation given.	Yes	
5.12	Certificate from the applicant in the following format.		
	I) Laying of Electrical cable line will not have any deleterious effects on any of the bridge components and road way safety for traffic.	Yes	
	II)For 6 lanning we do undertake that I will reincate service road/approach road/utilities at our own cost not standing the permission granted within such time as will be stipulated by NHAI for future six-lanning or any other development.	Yes, It will be certified.	
6	Who will sign the agreement	Executive Engineer, TPNODL, Joda Electrical Division, Joda	
7	Certificate from the Project Director.	NA	
7.1	Certificate for confirming of all standard condition issued vide ministry Circular No NH-41(581/68 dated 31.01.4969,Ministry circular no NH-III/P/66/76 dated 18/19.11.1976, Ministry circular no RW/NH-III/P/66/76 dated11.05.1982' Ministry circular noRW/NH-11037/1/86/DOI dated 19.01.1995, Ministry circular no RW/NH-34066/2/95/S&R dated 25.10.1999 & Ministry circular no RW/NH-34066/7/2003 S&R (B) dated 17.09.2003.	Enclosed	
7.2	Certificate from PD in the following format.		
	I) It is certified that any other location of the electrical cable would be extremely difficult unreasonable costly and the installation of Water Supply pipe line/Electrical Cable within ROW will not adversely affect the design,	Enclosed	

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader

Executive Engineer
Joda Electrical Division
TPNODL, Joda

S.no	ITEM	Information/Status	Remarks
	stability & traffic safety such as widening of the carriageway, easing of curve etc.		
	II) For 6-Lanning.	NA	
	a) Where feasibility is available I do certify that there will be no hindrance to proposed six-lanning structures at the said location.		
	b) In case feasibility report is not available I do certify that sufficient ROW is available site for accommodating proposed six lanning.		
8	If NH section proposed to be taken up by NHAI on BOT basis a clause is to be inserted in the agreement." The permitted Highway on which licensee has been granted the right to pay cable/duct has also been granted as right of way to the concessionaire the concession agreement for up-gradation of... NH no 215 on buide,operate and transfer basis and therefore, the licensee shall honour the same	We will honor NHAI Guidelines	
9	Who will supervise the work of laying of UG Electrical cable use.	Executive Engineer, TPNODL, Joda Electrical Division, Joda	AE of NHAI
10	Who will ensure that the defects in road portion after laying of Electrical cable line are corrected and if not corrected then what action will be taken.	Executive Engineer, TPNODL, Joda Electrical Division, Joda	AE of NHAI
11	Who will pay the claims for damages done/disruption permission in the concessionaire if asked by the concessionaire?	Executive Engineer, TPNODL, Joda Electrical Division, Joda	
12	A certificate form PD that he will enter the proposed permission in the register of records of the permissions in the register of the permissions in the prescribed proforma (copy enclosed)	NA	
13	If any previous approval is accorded for laying of underground water supply pipe line/Electrical Cable then Photocopy of register of records of permissions accorded as maintained by PD then copy be enclosed.	NA	

Thanking you.

Yours Faithfully,

Executive Engineer (Electrical)

JoED, Joda.

Executive Engineer
Joda Electrical Division
TPNODL, Joda

L. N. Malviya Infra Projects Pvt. Ltd.

Acting Team Leader