

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण
(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)
National Highways Authority of India
(Ministry of Road Transport & Highways, Government of India)
क्षेत्रीय कार्यालय, मदुरै / Regional Office, Madurai

दूसरा व तीसरी तल, विजय कृष्ण प्लाज़ा, संख्या-1, लेक एरिया, मेलूर मेन रोड, माट्टुतावनी, मदुरै-625 007
2nd & 3rd Floor, Vijay Krishna Plaza, No.1, Lake Area, Melur Main Road, Mattuthavani, Madurai-625 107
दूरभाष/Tele : +91-452-258 8999 वेब/Website : www.nhai.gov.in ई-मेल/E-mail : romadurai@nhai.org



NHAI/15018/4.2/16/2022/RO Madurai/E:170328 / 117

24th January, 2023

INVITATION OF PUBLIC COMMENTS

Sub: NHAI-PIU, Madurai- "PIU, Karaikudi - Laying of water supply pipeline of size various Dia HDPE pipeline along the road from Km.119/000 to Km.124/000; Km.125/130 to Km.126/800 (RHS) for a length of 6.670Kms and from Km.119/150 to Km.119/800 (LHS) for a length of 0.650Km by open Trench method & across the road in 6 locations at Km.118/200, Km.118/650; Km.119/800; Km.124/300; Km.124/750 & Km.126/800 by Trenchless Method in Thirumayam - Manamadurai section of NH 226 in the State of Tamil Nadu - Invitation of Public Comments - Reg.

The proposal received from PD, Madurai vide letter No. PD, Karaikudi LrNo. NHAI/PIU/Karaiudi/11034/TM/TWAD/2022/1760 dated. 20.09.2022 there by requesting permission for laying of laying along the road from Km.119/000 to Km.124/000; Km.125/130 to Km.126/800 (RHS) for a length of 6.670Kms and from Km.119/150 to Km.119/800 (LHS) for a length of 0.650Km & across NH at Km.118/200, Km.118/650; Km.119/800; Km.124/300; Km.124/750 & Km.126/800 in Thirumayam - Manamadurai section of NH 226 in the State of TamilNadu proposed by, Executive Engineer, TWAD Board, Project Division, Karaikudi. in accordance with Ministry's latest guidelines dated 22.11.2016.

2) The alignment proposed by the, Executive Engineer, TWAD Board, Urban Division, Karaikudi. requesting permission for laying of laying along the road from from Km.119/000 to Km.124/000; Km.125/130 to Km.126/800 (RHS) for a length of 6.670Kms and from Km.119/150 to Km.119/800 (LHS) for a length of 0.650Km & across NH at Km.118/200, Km.118/650; Km.119/800; Km.124/300; Km.124/750 & Km.126/800 in Thirumayam - Manamadurai section of NH 226 in the State of TamilNadu detailed under;

Stretch in Km	Length in Meters	Dia of pipe	Available ROW (in Meter)	Distance of erection from C/L (in Meter)		Remarks
				LHS	RHS	
Along NH-226 Km119+000 to Km 124+000(RHS)	5000	160 mm	30	-	14.50	Laying of pipe line along the extreme edge of ROW at a distance of 0.5m from ROW edge.

NHA/15018/4.2/16/2022/RO Madurai/E:170328 / 117

24th January, 2023

Along NH-226 Km125+130 to Km 126+800(RHS)	1670	75 mm	30	-	14.50	Laying of pipe line along the extreme edge of ROW at a distance of 0.5m from ROW edge.
Along NH-226 Km119+150 to Km 119+800(LHS)	650	110 mm	30	14.50	-	Laying of pipe line along the extreme edge of ROW at a distance of 0.5m from ROW edge.
Across NH-226 Km.118/200	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.
Across NH-226 Km.118/650	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.
Across NH-226 Km.119/800	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.
Across NH-226 Km.124/300	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.
Across NH-226 Km.124/750	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.
Across NH-226 Km.126/750	30	200	30	-	-	Laying of pipe line across by HDD Method at a depth of 1.60m below the top Sub grade.

3) Executive Engineer, TWAD Board, Project sub Division, Karaikudi has mentioned that the Water supply pipeline along the NH by Open Trench Method at a depth of



National Highways Authority of India

NHAI/15018/4.2/16/2022/RO Madurai/E:170328 / 117

24th January, 2023


more than 1.20m from ground level for along portion and by HDD at a depth of 1.60m for ground level for across portion.

4) Executive Engineer, TWAD Board, Project Division, Karaikudi, has furnished an undertaking to the effect that the applicant will remove the laid Water supply pipeline in future if required by NHAI/MoRTH, Govt. of India at any time for expansion of the NH at their own cost.

5) Accordingly, as per Policy Guidelines issued by Ministry vide letter No. RW/NH-33044/29/2015/S&R(R) dated 22.11.2016., the application is being uploaded on public domain for 30 days for seeking claims and objections (on grounds of public inconvenience, safety and general public interest).

The Regional Officer,
National Highways Authority of India,
No.2nd & 3rd Floor, Vijay Krishna Plaza,
No.1, Lake Area, Melur Main Road, Mattuthavani,
Madurai - 625 007.

Yours Faithfully,


24/01/2023
(Umesh K Garg),
Dy. General Manager (Tech.,)

Copy to:

1. The NIC, New Delhi - for uploading in the Ministry's website.
2. The PD, Karaikudi - for information.