

भारतीय राष्ट्रीय राजमार्ग प्राधिकरण (सङ्क परिवहन और राजमार्म मंत्रालय) National Highways Authority of India (Ministry of Road Transport & Highways) क्षेत्रीय कार्यालय, मदुरे / Regional Office, Madurai दूसरा व तीसरी तल, विजय कृष्ण प्लाज़ा, संख्या-1 लेक एरिया, मेलूर मेन रोड, माहुतावनी, महूरे-625 107 2" & 3" Floor, Vijay Krishna Plaza, No.1, Lake Area, Melur Main Road, Mattuthavani, Madurai-625 107



NHAI/15018/4.4.3/2019/ RO Madurai/E:96983/1454

16th August 2021

Invitation of Public Comments

Sub: NHAI, Madurai Region - Highway Administration - Permission for laying of water Pipe line under PIU, Karaikudi - laying Water pipe line by TWAD Board, Project Division, Sivagangai Along the Road at Km134/430 to 134/550 (RHS) & Km.134/550 to Km.150/930 (LHS); across the road at Km.124/700 & Km.134/550 and Across the road crossing at Km.137/150 (LHS); Km.140/020 (LHS) on Thanjavur - Manamadurai section of NH-226 in the state of Tamilnadu.

 A proposal was received from the Executive Engineer, TWAD Board, Project Division, Sivagangai regarding laying water supply pipeline along the road from Km134/430 to 134/550 (RHS) & Km.134/550 to Km.150/930 (LHS) by Open trench method; across the road at Km.124/700 & Km.134/550 and Across the road crossing at Km.137/150 (LHS); Km.140/020 (LHS) by HDD method on Thanjavur - Manamadurai section of NH-226 in the state of Tamilnadu i.e., in a length of 16500m.

S.No.	Village Name	Chainage in Km.		Length	Side
		From	То	(m)	
1	Kadambankulam	134.430	134.550	120	RHS
2	Kadambankulam	134.550	136.140	1590	LHS
3	Keelakandani	136.140	137.550	1410	LHS
		137.550	138.100	550	LHS
4	Sundaranadappu	138.100	141.090	2990	LHS
5	Kattoorani	141.090	147.350	6260	LHS
		147.350	150.000	2650	LHS
6	Surakulam	150.000	150.800	800	LHS
7	Seikkalathur	150.800	150.930	130	LHS
8	Crossing				
1	Solapuram	124.700		30	-
2	Kadambankulam	134.550		45	-
3	Keelakandani	137.150		45	-
4	Sundaranadappu	140.020		45	-
Total				16665	

2. The proposed location are as hereunder:

- 3. Water supply pipeline will be laid more than 1.30m below Ground Level as per the Ministry stipulation of minimum 1.20 meter below the ground level.
- 4. Crossing Proposed by trenchless method (HDD) with encasing pipeline for the entire NH RoW. The encasing pipe will be laid at 1.55 below Ground Level as per the Ministry stipulation of minimum 1.20 meter below the ground level.
- 5. The land acquisition for the project of two laning of Thirumayam Manamadurai has done as per NHAI LA Policy of 45.0m RoW for bypasses stretch & 30.0m RoW for existing road widening stretch. The proposed water supply pipeline shall be located, beyond the toe line of the embankment and drains, as close to the extreme edge of the RoW within the utility corridor.

A copy of drawing showing proposed alignment is enclosed herewith for information.

Comments of the public on the above proposal are invited and the same may be communicated to

The Regional Officer, National Highways Authority of India, 2nd & 3rd Floor, Vijay Krishna Plaza, No.1.Lake Area, Melur Main Road Mattuthavani, Madurai-625017.

This is issued with the Approval of Competent Authority

Yours Sincerely,

Encl: As Above.

(MS Chaithanya) Manager (Tech)

Copy to:

- 1. The NIC, New Delhi for uploading in the Ministry's website
- 2. PD PIU Karaikudi.
- 3. M/s Executive Engineer, TWAD Board, Project Division, Sivagangai.