



**भारतीय राष्ट्रीय राजमार्ग प्राधिकरण**  
(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)  
**National Highways Authority of India**  
(Ministry of Road Transport & Highways, Govt. of India)  
क्षेत्रीय कार्यालय : एफ-120, जनपथ, श्याम नगर, जयपुर-302019  
Regional Office : F-120, Janpath, Shyam Nagar, Jaipur-302019  
Tel. (O) / फोन : (ऑ.) 0141-2292056, 2292049  
E-mail / ई-मेल : rojaipur@nhai.org Web. / वेब : www.nhai.gov.in



क्रमांक:NHAI/18013/1/2021-ROJ/Permission-Laying-Sewer Pipeline/RUIDP/294/NH-58, km 177.12 to 179.35/2190 दिनांक: 31.10.2023

**INVITATION OF PUBLIC COMMENTS**

**विषय:** Proposal for grant of permission for laying RCC 600mm dia Sewer Pipeline along Salasar-Nagaur section of NH-58 from Km. 177.120 to 179.350 (RHS) (total length 2230m) in the state of Rajasthan by RUIDP - reg.

**सन्दर्भ:** 1. EE, RUIDP letter no. 876 dated 17.01.2023 and letter no. 975 dt. 29.03.2023 and letter no. 1048 dated 13.06.2023 and letter no. 1669 dated. 21.09.2023.  
2. PD, PIU-Jaipur letter no. NHAI/JPR/S.O. Sikar/SN/Crossing/2023-24/1713 dt. 12.10.2023 (received on 16.10.2023).

Sir,

It is to inform all concern that Ex. En., RUIDP, Ladnu (Rajasthan) vide letter under reference (1) above has submitted a proposal for the subjected work and PD, NHAI, PIU, Jaipur has submitted the above proposal vide letter under reference (2) for approval of the Competent Authority, Highway Administration.

2. The proposal is regarding grant of permission for laying RCC 600mm dia Sewer Pipeline along Salasar-Nagaur section of NH-58 from Km. 177.120 to 179.350 (RHS) (total length 2230m) in the state of Rajasthan by RUIDP.

3. As per Para-4 of Ministry's Circular No. RW/NH-33044/29/2015S&R(R) dated 22.11.2016, the Highway Administration shall be put out in the public domain for 30 days for seeking claims and objections (on grounds of public inconvenience, safety and general public interest).

4. In view of the above, before approval of the competent authority, the comments/objections of affected public is hereby invited with reference to the Ministry's circular dated 22.11.2016 due to laying of Sewer Pipeline along the subjected stretch. The objections/comments may be addressed to the below mentioned address upto 30.11.2023, beyond due date, no comments/objections will be accepted.

**The Regional Officer, Regional Office - Jaipur**  
National Highways Authority of India,  
F-120, Janpath, Shyam Nagar, Jaipur (Raj.)-302019,  
Tel : 0141-2292049, 2292054 Email : rojaipur@nhai.org

This issues with the approval of Highway Administration-cum Regional Officer, NHAI, Jaipur

भवदीय,  
  
(मनमोहन खोसला)  
प्रबन्धक (तकनीकी)

**Copy to:** (i) Web Admn., NHAI, HQ, New Delhi - for uploading in NHAI's website [web-admin@nhai.org]  
(ii) Director, NIC, New Delhi - for uploading in Ministry's website. [mansoor@nic.in]  
(iii) PD, PIU-Jaipur: for information.  
(iv) Ex. En., RUIDP, Ladnu (Rajasthan): for information.



# भारतीय राष्ट्रीय राजमार्ग प्राधिकरण

(सड़क परिवहन और राजमार्ग मंत्रालय, भारत सरकार)

## National Highways Authority of India

(Ministry of Road Transport & Highways, Government Of India)

परियोजना कार्यान्वयन इकाई, जयपुर/ Project Implementation Unit, Jaipur

डी-148, आर. एस.ई.बी. सब-स्टेशन के पीछे, वैशाली नगर, जयपुर-302021

D-148, Behind RSEB Sub-Station, Vaishali Nagar, Jaipur-302021

दूरभाष / Phone : 91-141 - 4026465, ई-मेल / E-mail : jai@nhai.org



No. NHAI/JPR/S.O. Sikar/SN/Crossing /2023-24/ 1713

Date: 12.10.2023

Regional Officer,  
National Highway Authority of India  
Regional Office,  
F-120 Janpath Shyam Nagar  
Jaipur-302019



MTT-MK  
17/10  
sknd(MK)  
17/10

**Project:** Development and Construction of Two Laning with paved shoulder for up-gradation of Salasar-Nagaur section of NH-65 (New Nh-58) in the state of Rajasthan (Group A-Package 2) Design chainage from km. 151.141 to design chainage km. 270.735 on Hybrid Annuity Mode-[UPC : N/08004/5001/RJ]

**Subject:-** Permission for laying RCC 600 MM Dia sewer pipe along with NH-58-reg.

- Ref:- [1] Executive Engineer RUDIP, Ladnu letter no.876 dated 17.01.2023  
[2] This office letter no. 763 dated 23.01.2023  
[3] IE letter no.- FIPL/NHAI/IEOM/ROJPR/Reengus/242 dated 14.02.2023  
[4] This office letter no. 851 dated 14.03.2023  
[5] Executive Engineer RUDIP, Ladnu letter no. 975 dated 29.03.2023  
[6] Site Inspection dated 27.04.2023  
[7] This office letter no. 367 dated 25.05.2023  
[8] Executive Engineer RUDIP, Ladnu letter no.1048 dated 13.06.2023  
[9] SE, RUIDP, Kuchaman letter no. 1669 dated 21.09.2023

Sir,

Reference is invited to Executive Engineer RUIDP, Ladnu letter dated 17.01.2023 & 21.09.2023 vide which said proposal has submitted to this office for permission for laying RCC 600 MM Dia sewer pipe along with NH-58.

2. The said proposal has visited along with the representative of IE for the subjected proposal & found that:-

- Undertaking, check list, drawing, etc. are as per requirement.
- Total length of sewer pipeline proposed along the NH route is 2.23 km. (ch. 177.120 to 179.350) and 200 meter (ch. 179.350) at Mega Highway link.
- Applicant shall be responsible for any damage of Project Highway including ROW and shall restore the Project Highway and ROW to its original condition.

3. Further, this office has requested EE, RUIDP, Ladnu to submit the BG and License Fee as per MoRTH guideline dated 22.11.2016. EE, RUIDP, Ladnu vide letter dated 13.06.2023 & 02.09.2023 has deposited License fee to 'BharatKosh' receipt no. 0906230009686 dated 09.06.2023 and Bank Guarantee amounting to Rs. 12.64 Lacs/- in favour of NHAI, the same has been confirmed by the Canara Bank.

4. Hence, in view of above, the proposal of permission for laying RCC 600 MM Dia sewer pipe along with NH-58 is hereby recommended for approval.

Encl- As above

Yours Faithfully,

0217  
Project Director 12/10

## CHECK- LIST

Guidelines for processing the proposal for laying of Utility line in the land along National Highways vested with NHAI.

General Information		
1	Name & Address of Applicant/Agency	Rajasthan Urban Infrastructure Development Project (RUIDP), Ladnun
2	National Highway No.	NH-58
3	State	Rajasthan
4	Location	Ladnun, Nagaur (Rajasthan)
5	Chainage in KM	177/120 to 179/350
		200 Mtr Mega Highway Link attached at Chainage 179/350
6	Length in m	177/120 to 179/350 at NH 58 - 2230 Meter
6		Mega Highway Link attached at 179/350 – 200 Meters (Total – 2230 + 200 = 2430 Meters)
7	Width of Available ROW on both sides	45.0 mtr at NH 58 & 30 mtr at Link Road
8	Side of NH (Left or right side of NH toward increasing chainage/KM direction)	Right Side
9	Name of Highway Authority of NHAI/PWD/BRO	NHAI
10	Highway Administration address	The Highway Administration Cum Chief Engineer & RO, MoRTH DCM, Ajmer Road, Jaipur - 302019.

*Signature*  
Sd/-

*Signature*

*Signature*  
परियोजना निदेशक / Project Director  
भारत प्रा. एकाई / NHAI PIU, Jaipur  
EXECUTIVE ENGINEER  
R.U.I.D.P. PHASE - IV  
LADNUN (RAJ.)

S. No	Item	Measurement. Observations as per site conditions	MORTH Norms	Whether complying with MORTH Norms
1	Details of already laid utility service, if any	-	Enclosed	
2	Whether up gradation of the stretch in near future is proposed or not	-		
	(a) If yes, provision of utility adversely affects the plan of up-gradation	-	Not affect plan of up-gradation	
3	<b>Laying of the utility service along the National Highways.</b>	-		
3.1.	Location of proposed utility service along the stretch	RHS	Utility Duct/ beyond the toe line of the embankment and drains, and close to the extreme edge of the RoW.	
3.2	Depth of top of utility service from ground level	3.00 to 3.5 mtr	0.6 meter	
3.3	Mechanism for crossing water channel	NA	Through utility duct (if provision exists) or beneath the bed of water channel	
3.4	Whether ROW is restricted in this stretch?	-		
3.4.1	If yes, whether provision of land acquisition is required to lay utility	NA		
	(a) If yes, whether undertaking for land acquisition along with relevant L.A. details has been furnished	NA		
3.4.2	Width of concrete duct, if utility services are proposed to be laid in concrete ducts	NA	NA	
4	<b>Laying of utility services across the NH</b>	NA		
4.1	Whether Existing drainage structures is allowed to carry the utility lines.	NA	Not allowed	
4.2	Proposed crossing of utility service	NA	Perpendicular to NH	
4.3	Type of casing pipe/conduit carrying the utility line.	NA	MS Casing	
4.4	Whether ends of the casing/conduit pipe are sealed from the outside	NA	Sealed	

022  
 प.रेयोजना निदेशक / Project Director  
 भाराराप्रा, प.का.ई. / NHAI PIU, Jaipur  
 EXECUTIVE ENGINEER  
 R.U.I.D.P. PHASE - IV  
 LADNUN (RAJ.)

Site Engineer



4.5	Length of casing/conduit pipe crossing NH.	NA	60m	
4.6	Depth of top of the casing/conduit pipe.	NA	At least 1.2 m below the top of subgrade	
4.7	Crossing method in case of CC pavement.	NA	Trenchless (HDD)	
4.8	Horizontal and vertical clearances in case utilities are allowed overhead,	NA	In accordance with IRC codes.	
5	<b>Document / Drawings enclosed with the proposal</b>	Yes		
5.1	Cross-Section showing the size of trench for open trenching method	Enclosed	Enclosed, if applicable	
	(a) Trench width	1.45 Mtr	More than 30 cm and less than 60 Cm wider than the outer diameter of the utility pipe	
	(b) Filling of trench	As per Guideline	as per Ministry guidelines vide letter No. RW/NH-34044/29/2015/S&R (R) dated 22.11.2016	
	(c) location of trench	RHS side of the ROW	extreme edge of the ROW	
5.2	Cross section showing the size of pit and location of conduit for HDD method	Enclosed	Enclosed	
5.3	Strip plan/ Route plan showing utility line, chainage, width of ROW, distance of proposed utility from the edge of ROW, important mile stone, intersections, cross drainage works etc.	Enclosed	Enclosed	
5.4	Plan and profile drawing of stretch showing cross section of road at 20m distance along with ROW and proposed utility	Enclosed	Enclosed	02m
6	Methodology for laying of utility line	Enclosed	Enclosed	
7	Draft License Agreement is as per Ministry guidelines vide letter No. RW/NH-34044/29/2015/S&R (R) dated 22.11.2016 and signed by two witnesses	Enclosed	Enclosed	
8	License fees in Favor of MoRTH RPAO Jaipur	Enclosed	As per Ministry vide circular no. RE/NH	

Site Engineer  
Ajay

EXECUTIVE ENGINEER  
R.U.I.D.P. PHASE - IV  
LADNUN (RAJ.)

निदेशक / Project Director  
भाराराप्ता, प.का.ई. / NHAI PIU, Jaipur


			33044/29/2015/S&(R)dated 22.11.2016	
9	Whether Bank Guarantee has been obtained	Yes	As per Ministry vide circular no. RE/NH-33044/29/2015/S&(R)dated 22.11.2016	
	(a) If yes, whether Confirmation of BG has been obtained as per MoRTH/NHAI guidelines	Yes		
10	<b>Affidavit / Undertaking from the Applicant for</b>			
10.1	Undertaking for not to damage other existing utility, if damaged then to pay the losses to either to MoRTH/NHAI or to the concerned agency.	Enclosed	Enclosed	
10.2	Undertaking for renewal of Bank Guarantees and when asked by NHAI/ MoRTH	Enclosed	Enclosed	
10.3	Undertaking for confirming all standard condition of MoRTH/NHAI guidelines.	Enclosed	Enclosed	
10.4	Undertaking for shifting of utility as and when asked by MoRTH/ NHAI within a month at their own cost.	Enclosed	Enclosed	
10.5	Undertaking for indemnity against all damages and claims.	Enclosed	Enclosed	
10.6	Undertaking for management of traffic movement during laying of utility line without hampering the traffic.	Enclosed	Enclosed	
10.7	Undertaking that If any claim is raised by the Concessionaire/contractor then the same has to be paid by the applicant	Enclosed	Enclosed	
10.8	Undertaking that the applicant has obtained various safety clearances from the representative authorities such as directorate of Electricity, Chief controller of Explosives, Petroleum and Explosive Safety Organization, Oil Industry Safety Directorate, State/Central Pollution Control Board and any other statutory clearances applicable, before applying to Highway Administration	Enclosed	Enclosed	

*Sil Kumar*  
AM

*[Signature]*  
**EXECUTIVE ENGINEER**  
**R.U.I.D.P. PHASE - IV**  
**LADNUN (RAJ.)**

The Right of the Way (ROW) of the National Highway available at the proposed location from the center line of divided carriageway is 22.5 m (from center of ROW to edge of ROW towards proposed utility)

The above particulars along with the drawings and documents have been verified and certified as correct as per prevailing site conditions.

  
EXECUTIVE ENGINEER  
R.U.I.D.P. PHASE - IV  
LADNUN (RAJ.)

[Name Designation and signature of the authorized representative of applicant]

[Name Designation and signature of concerned field authority of NHAI/PWD/BRO]

  
Sd/- Engineer

Ajw



प्र.रेयोजना निदेशक / Project Director  
भाराराप्रा, प.का.ई. / NHAI PIU, Jaipur