



**भारतीय राष्ट्रीय राजमार्ग प्राधिकरण**  
(सड़क परिवहन और राजमार्ग मंत्रालय)  
**National Highways Authority of India**  
(Ministry of Road Transport & Highways)  
क्षेत्रीय कार्यालय, चेन्नई / **Regional Office, Chennai**  
'श्री टावर' 3<sup>rd</sup> मंजिल, DP-34 (SP), इंडस्ट्रियल एस्टेट, गिण्डी, चेन्नई - 600 032  
'SRI TOWER', 3<sup>rd</sup> Floor, DP-34 (SP), Industrial Estate, Guindy, Chennai - 600 032.

दूरभाष/Tele : 91-44-2225 2635  
फैक्स/Fax : 91-44-2225 2636  
ई-मेल/ E-mail: rochennai@nhai.org

NHAI/11019/16/2009/RO Chennai 983

4<sup>th</sup> March, 2020

**Invitation of Public Comments**

Sub: NHAI, RO, Chennai - PIU, Viluppuram – Balance Work of two laning with paved shoulders of Tindivanam to Krishnagiri Section of NH-66 from Km 37/600 to Km 219.782 under NHDP Phase-III in the State of Tamil Nadu on Item Rate Contract – Laying of Underground OFC on NH-66 along the road from Km 178/750 to Km 180/244 and from Km 0/000 to Km 1/992 (RHS) in Samalpatti Town and across at km 178/750 by M/s. Vindhya Telelinks, Chennai – Regarding.

The proposal is regarding permission for laying of Optical Fibre Cable Tindivanam to Krishnagiri Section of NH- 66 from Km 178/750 to Km 180/244 and from Km 0/000 to Km 1/992 (RHS) for a total length of 3486 m in Samalpatti Town and across at km 178/750 by M/s. Vindhya Telelinks Limited, Chennai submitted to this office by the PD, NHAI, Viluppuram vide letter No. (393) dated 26.02.2020.

2. The available width of ROW is 28m (14 + 14) and it is proposed to lay the OFC at a distance of 13.5m on RHS from the centre line of the main carriageway.
3. M/s. Vindhya Telelinks Limited, Chennai has proposed to lay 20mm dia OFC Cable along the road by open trench method encased in 40mm dia duct duly keeping the top of the casing at 1.65 m below the ground level. Further the applicant has proposed to lay the 20mm OFC Cable across NH by HDD method, encased in 40mm Dia Duct, which in turn encased in 150mm RCC casing pipe duly keeping the top of the casing pipe at a depth of 1.65 m below the ground level.
4. M/s. Vindhya Telelinks Limited, Chennai has furnished an undertaking to indemnify the concerned agency in coordination with NHAI, against all damages and claims, if any, due to the digging of trenches for laying cables/ducts. Further, the applicant has furnished undertaking that they will adopt HDD method wherever, the available width of ROW is less than 15 m and undertaking not to damage other utility, if damaged, then to pay the losses either to NHAI or to the concerned agency
5. As per the guidelines issued by the Ministry vide letter No. RW/NH-33044/29/2015/ S&R(R) dated 22.11.2016, the proposal submitted by M/s. Vindhya Telelinks Limited, Chennai will be made available for 30 days seeking public


# National Highways Authority of India

comments/objections and the comments shall be furnished within 30 days from the day of closure of public objections.

In view of the above, comments of the public on the above proposal are invited and may be sent to the below mentioned address:

The Regional Officer  
National Highways Authority of India  
(Ministry of Road, Transport & Highways)  
SRI Tower, 3rd Floor  
DP - 34 (SP), Industrial Estate,  
Guindy - Chennai-600 032

Yours faithfully,

  
(A. Savithri Devi)

Deputy General Manager (Tech)  
For Regional Officer, NHAI, Chennai

**Copy to:**

1. NHAI website
2. The NIC, New Delhi - for uploading in the Ministry's website.
3. PD, NHAI, Viluppuram – for information